



भा.कृ.अनु.परिषद – केन्द्रीय आलू अनुसंधान संस्थान (क्षेत्रीय केन्द्र)

पोस्ट बैग न0. 1, मॉडल टाउन डाक घर, जालंधर - 144003

ICAR-Central Potato Research Institute (Regional Station)

Post Bag No. 1, Model Town P.O. Jalandhar 144 003

Tel: 0181-2791474, Fax: 0181-2790863, email: jalandhar.cpri@icar.gov.in



पत्रांक X 12020/जालंधर/रिपेयर ऑफ Seed Section/ 1845

दिनांक: 29/01/24


निविदा आमंत्रण सूचना

केन्द्रध्यक्ष, भा.कृ.अनु.परि-केन्द्रीय आलू अनुसंधान संस्थान (क्षेत्रीय केंद्र), जालंधर द्वारा निम्नलिखित कार्य के लिए निम्न निबंधन व शर्तों के आधार पर E-Procurement के अनुरूप निविदाएं आमन्त्रित की जाती हैं। निविदा के नियम/शर्तों के विवरण की जानकारी संस्थान की वेब-साईट <http://cpri.gov.in> अथवा भारत सरकार वेबसाईट <https://eprocure.gov.in/eprocure.app> से डाउनलोड की जा सकती है।

क्र० स०	कार्य का नाम
01	Repair /renovation of Seed Section at CPRS Jalandhar (Specification enclosed)
Tender ID	2024_SARE_792583_1
Last Date for submission of quotations	20 February, 2024 (Tuesday)
Date for opening of quotations	22 February, 2024 (Thursday)

1. निविदा Online-procurement के माध्यम से भेजनी होगी, Offline निविदाओं पर विचार नहीं किया जाएगा।
2. Online निविदा दिनांक **20 February, 2024, दोपहर 2.30** बजे सीपीपी पोर्टल पर प्राप्त होनी चाहिए। निर्धारित समय/तिथि के बाद प्राप्त हुई निविदाओं पर विचार नहीं किया जाएगा।
3. निविदाओं के साथ 20,000/- रुपये की धरोहर राशि डिमांड ड्राफ्ट के रूप में आवश्यक रूप से प्राप्त होनी चाहिए, जो CPRS, Jalandhar (State Bank of India, Khurla Kingra Branch, IFSC कोड नंबर SBIN0002394) के नाम जमा करवानी होगी और अंतिम तारीख से पहले-पहले original ड्राफ्ट या MSME सर्टिफिकेट कार्यालय में पहुँचना चाहिए अन्यथा निविदा पर विचार नहीं होगा।
4. निविदा डालने वाली फ़र्म CPWD/PWD or other Central/State Govt agencies से registered होनी चाहिए और उनके द्वारा रजिस्ट्रेशन प्रमाण पत्र EMD के ड्राफ्ट की प्रति व अन्य दस्तावेज़ की scanned copy CPP portal पर अवश्य अपलोड की जानी चाहिए।
5. दरें सभी करों सहित होनी चाहिए तथा आदेशित कार्य केंद्र में करना होगा।
6. किसी प्रकार की कटिंग व ओवर राइटिंग (cutting and over writing) होने पर अपने हस्ताक्षर करें।

7. फर्म इस बात का ध्यान रखें कि दी गई दरें 90 दिनों तक मान्य होनी चाहिए । सभी quoted रेट में cost and supply of all materials at site, including all taxes, service tax, transportation of material and labour charges etc for each item of work शामिल होने चाहिये ।
8. कार्य में इस्तेमाल होने वाले सामान की गुणवत्ता नामित अधिकारी द्वारा जांच करने के बाद ही प्रयोग में लाया जा सकेगा ।
09. जो फर्म दिशा निर्देश का उल्लंघन करेगी उसकी/उनकी निविदा पर विचार नहीं किया जाएगा।
10. इस कार्य के लिए कोई अग्रिम भुगतान नहीं किया जाएगा। कार्य संतोषजनक पूर्ण होने के बाद बिल का भुगतान applicable TDS काटने बाद फर्म के खाते में online जमा किया जाएगा, जिसके लिए फर्म कार्य समाप्ति पर बिल, पूरे बैंक डीटेल के साथ कार्यालय में जमा करवाएगा । अतः including Tax/GST जो देय है साफ साफ लिखा जाए । इस संबंध में कार्यालय की ओर से कोई भी C & D Form अलग से नहीं दिया जावेगा।
11. कार्य आदेश मिलने के बाद 45 दिन के भीतर उक्त कार्य खत्म करना होगा ।
12. उपरोक्त सबन्धित सामान की दरे F.O.R.CPRS, Jalandhar तक होनी चाहिए, कार्यालय की तरफ से कोई किराया भाड़ा नहीं दिया जाएगा ।
13. उपरोक्त कार्य के लिए कार्य-स्थल की Physical Verification के लिए किसी भी कार्य दिवस में सुबह 10 बजे से साय: 4 बजे तक श्री अनिल कुमार चंदेल, STA, इलैक्ट्रिकल (दूरभाष-9877822271) से संपर्क किया जा सकता है।
14. अधोहस्ताक्षरी किसी भी या सारी निविदाओ को बिना किसी कारण रद्द करने का अधिकार रखते हैं।


(प्रमुख)

वितरण:

1. श्री अखिलेश कुमार सिंह, ACTO, सीपीआरएस, जालंधर को e-portal पर अपलोड करने हेतु
2. In-charge AKMU Cell, ICAR-CPRI, शिमला को वैबसाइट पर अपलोड करने हेतु
3. श्री अनिल कुमार चंदेल, STA, इलैक्ट्रिकल ICAR-सीपीआरएस, जालंधर

ESTIMATE

Name of work: Repair and renovation Seed section at CPRI(RS) Jalandhar.

SN	Item of work	Qty	Rate	Unit	Amount(Rs)	Remarks
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete	400.00 m2				
2	Distemping with 1 st quality acrylic distemper (ready made) having VOC content less than 50 gm per ltr. Of approved manufacturer and of required shade and colour complete. As per manufacturer's specification. (A) Old work (one or more coats)	1474.00 m2				
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade (A) One or more coats on old work	90.00 m2				
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer. Over the plastered wall surface to prepare the surface even and smooth complete.	400.00 m2				
5	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface (A) Water thinnable cement primer	400.00 m2				
6	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade Two or more coats on new work	532.00 m2				
7	12 mm cement plaster of mix 1:6 (1 cement : 6 fine sand)	30.00 m2				
8	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6(1 cement : 6 fine sand)	30.00 m2				
9	Providing & fixing of PVC wall panelling complete in all respect wit necessary beading as per the direction In-charge Engineering Section.	54.49 m2				
10	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand(zone-II) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	0.20 m3				

Handwritten signature

11	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	20.00 kg			
12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.				
12A	25 mm dia nominal bore	6.00 mt			
12B	32 mm dia nominal bore	6.00 mt			
12C	50 mm dia nominal bore	6.00 mt			
13	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern	2.00 No			
14	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40 mm flush bend, 20 mm over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: White vitreous china dual purpose WC pan with white solid plastic seat and lid with white vitreous china flushing cistern and C.P. flush bend.	1.00 No			
15	Providing and fixing automatic sensor glass door with toughened glass 12 mm thick with necessary fitting etc. complete as per direction of Engineer in-charge	6.50 m2			
	Providing and fixing toughened glass 12 mm thick with necessary fitting etc. complete as per direction of Engineer in-charge	5.00 m2			
16	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drain (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift up to 1.5 m , including getting out the excavated soil as directed , with in a lead of 50 m. (A) All kinds of soil.	2.00 m3			
17	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material	3.00 m3			

Handwritten signature

	within 50 metres lead as per direction of Engineer-in-charge. In cement mortar					
18	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite stone slab colour black, Cherry/Ruby red Area of slab over 0.50 sqm	10 m2				
	Total					
	Add 20.14% Cost Index on rates of D.S.R. – 2023 Rs					
	Grand Total Rs.					

1/1/2024

Estimate of seed section electrical work

1.	Wiring for light points/fan points/exhaust fan points with 1.5 sq mm FR PVC insulated copper conductor single/multi core cable in surface/ recessed steel conduits, with modular switches, modular plates, suitable GI box and earthing the point with 1.5 sq mm, FR PVC insulated copper conductor single /multi core cable etc. as required.	10			
2.	Supplying, Installing, Testing and commissioning of LED Pannel lights of 40 watt, Size 24"X24" with metal and glass construction with connection with 1.5sq mm copper conductor cable complete etc as reqd. (Trilux /Wipro and any equivalent brand)	10			
3.	Supplying , installation, testing and commissioning of Exhaust fan, with 1.5 sq mm FRLS PVC Insulated, copper conductor cable etc as reqd.	02			
8	Supplying, Installing, Testing and commissioning of LED bed lights of 10/14w watt, with metal and glass construction with connection with 1.5sq mm copper conductor cable complete etc as reqd. (Trilux /Wipro and any equivalent brand)	10			
	Total				
	Add 20.14% Cost Index on rates of D.S.R. – 2023 Rs				
	Grand Total Rs.				

Signature