

भा.कृ.अनु.परि-केंद्रीय आलू अनुसंधान संस्थान (क्षेत्रीय केंद्र)

बादशाहपुर, नकोदर रोड, जालंधर (पंजाब)-144026



ICAR- Central Potato Research Institute (RS)

Badshahpur, Nakodar Road Jalandhar (Pb)-144026

Ph. No.0181-2791474, 2790863, Email: Jalandhar.cpri@icar.gov.in



पत्रांक X 12020/जालंधर/RFS में अनुमोदित कार्य/ 1162

दिनांक: 13/11/24

निविदा आमंत्रण सूचना


केन्द्रध्यक्ष, भा.कृ.अनु.परि-केंद्रीय आलू अनुसंधान संस्थान (क्षेत्रीय केंद्र), जालंधर द्वारा निम्नलिखित कार्य के लिए निम्न निबंधन व शर्तों के आधार पर E-Procurement के अनुरूप CPWD/PWD/MES से Registered ठेकेदारों से online साथ संलग्न कार्य के ब्यौरे/estimate के अनुसार निविदाएं आमन्त्रित की जाती हैं। निविदा के नियम/शर्तों के विवरण की जानकारी संस्थान की वेब-साईट <http://cpri.gov.in> अथवा भारत सरकार वेबसाईट <https://eprocure.gov.in/eprocure.app> से डाउनलोड की जा सकती है।

कार्य का नाम Name of the work	Repair and Renovation of farm operation and service unit and tractor drivers' room at CPRI(RS), Jalandhar (साथ संलग्न कार्य के ब्यौरे/estimate के अनुसार)
Tender ID	2024-DARE-834749-1
ब्याना राशि Earnest Money Deposited (EMD)	Rs.6000/-
निविदा के प्रकार/Type of Tender	Open Tender (Single Bid)
कार्य समाप्त करने की समयवधि Duration of completion of work.	45 days
आपेक्षित दस्तावेज Documents required	BOQ uploaded Contractors Bank Details: Bank Account No., Bank Name, IFC code, PAN & GST No. Bid required with item wise rates alongwith BOQ Proof of valid Registration with CPWD/PWD/MES
Bid submission Start Date	14.11.2024 at 5:00 PM
Bid Submission Closing Date	05.12.2024 at 2:00 PM
Bid Opening Date	09.12.2024 at 2:30 PM

Terms & Conditions:

- निविदा Online-procurement के माध्यम से भेजनी होगी, Offline निविदाओं पर विचार नहीं किया जाएगा।
- निर्धारित समय/तिथि के बाद प्राप्त हुई निविदाओं पर विचार नहीं किया जाएगा।
- निविदाओं के साथ 6000/- रुपये की धरोहर राशि डिमांड ड्राफ्ट के रूप में आवश्यक रूप से प्राप्त होनी चाहिए, जो CPRI, Jalandhar (State Bank of India, Khurla Kingra Branch, IFSC कोड नंबर SBIN0002394)के नाम जमा करवानी होगी और अंतिम तारीख से पहले-पहले original ड्राफ्ट या MSME सर्टिफिकेट कार्यालय में पहुँचना चाहिए।

4. Performance security जोकि अनुमानित लागत की कुल 5 प्रतिशत राशि होगी जो कांट्रैक्ट खत्म होने की अर्द्धि के पश्चात 60 दिन तक रखी जाएगी । यह राशि Bank Draft/Bank Guarantee/FDR के रूप सफल ठेकेदार द्वारा कार्य आबंटन के 10 दिनों के भीतर कार्यालय में जमा करवानी होगी ।
5. दरें सभी करों सहित होनी चाहिए तथा आदेशित कार्य केंद्र में करना होगा ।
6. किसी प्रकार की कटिंग व ओवर राइटिंग होने पर अपने हस्ताक्षर करें।
7. फर्म इस बात का ध्यान रखें कि दी गई दरें 90 दिनों तक मान्य होनी चाहिए । सभी quoted रेट में cost and supply of all materials at site, including all taxes, service tax, transportation of material and labour charges etc for each item of work शामिल होने चाहिये ।
8. कार्य के क्रियान्वयन हेतु Estimate में दर्शाये गए सामान की गुणवत्ता से कोई भी समझौता नहीं किया जाएगा ।
9. जो फर्म दिशा निर्देश का उल्लंघन करेगी उनकी निविदा पर विचार नहीं किया जाएगा।
10. इस कार्य के लिए कोई अग्रिम भुगतान नहीं किया जाएगा। कार्य संतोषजनक पूर्ण होने के बाद बिल का भुगतान applicable TDS काटने बाद फर्म के खाते में online जमा किया जाएगा, जिसके लिए फर्म कार्य समाप्ति पर बिल, पूरे बैंक डीटेल के साथ कार्यालय में जमा करवाएगा । अतः including Tax/GST जो देय है साफ साफ लिखा जाए । इस संबंध में कार्यालय की ओर से कोई भी C & D Form अलग से नहीं दिया जावेगा।
11. उपरोक्त सबन्धित सामान की दरें F.O.R. CPRS, Jalandhar तक होनी चाहिए, कार्यालय की तरफ से कोई किराया भाड़ा नहीं दिया जाएगा ।
12. यदि ठेकेदार कोटेशन अपलोड करने से पहले कार्य का मुआइना करना चाहें तो वह अपने खर्च पर किसी भी कार्य दिवस में सुबह 10 बजे से साय: 4 बजे तक श्री अनिल कुमार चंदेल (दूरभाष 9877822271) एवं डॉ. कपिल कुमार शर्मा, CTO, (दूरभाष-9914757697) से संपर्क कर सकते हैं ।
13. यदि ठेकेदार या उनके कामगारों द्वारा संस्थान की प्रापर्टी को नुकसान पहुंचाया जाता है तो उस स्थिति में ठेकेदार को अपने खर्च पर भरपाई या मुरम्मत करनी होगी।
14. यदि कार्य के दौरान कार्यस्थल पर किसी मजदूर के साथ कोई दुर्घटना होती है तो उस स्थिति में ठेकेदार पूर्णतः उत्तरदाई होगा तथा ठेकेदार द्वारा सभी safety नियमों का पालन करना होगा ।
15. कार्यालय द्वारा जारी कार्य आदेश मिलने के बाद सात दिनों के भीतर ठेकेदार को अपनी सहमति इस कार्यालय में अवश्य देनी होगी ।
16. आबंटित कार्य प्रभारी (संपदा) अनुभाग की निगरानी में पूर्ण किया जाएगा ।
17. अधोहस्ताक्षरी किसी भी या सारी निविदाओं को बिना किसी कारण रद्द करने का अधिकार रखते हैं।


 13/11/24
 (प्रमुख)

वितरण:

1. In-charge AKMU Cell, ICAR-CPRI, शिमला को वेबसाइट पर अपलोड करने हेतु

ESTIMATE

Name of work: Repair and renovation of Farm operation service unit (Tractor garage) at CPRS Jalandhar, Punjab.

Part: I

SN	Item of work	Qty	Unit	Rs.	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repair to scratches etc. complete.	45 m2	sqm		
2.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer. Over the plastered wall surface to prepare the surface even and smooth complete.	45 m2	sqm		
3.	Distemping with 1 st quality acrylic distemper (ready mixed) having VOC content less than 50 gm per litre, of approved Brand and manufacturer including applying additional coats wherever required to achieve even shade and colour. (A) Old work (one or more coats).	150.00 m2	sqm		
4.	Providing and fixing aluminum work for doors, windows, ventilators, and partitions, with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS -733 and IS-1285, fixing with dash fasteners of required dia. and size, including necessary filling up the gaps at junctions, i.e. at top, bottoms and sides with required EPDM rubber / neoprene gasket etc. Aluminum section shall be smooth, rust free, straight, mitered, and jointed mechanically wherever required including cleat angle, Aluminum snap beading for glazing / paneling C.P. brass / stainless steel screws all complete as per architectural drawings and the direction of engineer- in-charge.(Glazing, paneling and dash fasteners to be paid for separately). (A) For fixed portion (a) Anodized aluminum (anodized transparent or dyed to required shade according to IS-1868, Minimum anodic coating of grade AC-15) (B) For shutters of doors, windows & ventilators including providing and fixing hinges, pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately(a) Anodized aluminum (anodized transparent or dyed to required shade according to IS-1868, Minimum anodic coating of grade AC-15)	75 Kg 125 Kg	Kg Kg		
5.	Providing and fixing 12 mm thick pre laminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminum doors, windows shutters and partitions frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge (A) Pre-laminated particle board with decorative lamination on both sides (Exterior grade)	06 m2	sqm		

Jalandhar

6.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	06 m2	sqm	
7.	Providing and fixing glazing in aluminium door, window, ventilator shutters and partition etc. with EPDM rubber / neoprene gasket etc. complete as per architectural drawings and the direction of Engineer-in-charge. (A) With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	04 m2	sqm	
8.	Providing and fixing aluminium hanging floor door stopper ISI mark anodized (anodic coating not less than grade AC-10 as per IS-1868) transparent or dyed to required Colour or shade with nuts and screws etc. complete (Twin rubber stopper)	04 nos.	each	
9.	Providing and fixing extruded section body tubular type universal hydraulic door closer (having brand logo with IS: 3564, embossed on the body, door weight up to 36 kg to 80 kg (and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	04 nos.	each	
10.	Providing and fixing 100 mm brass locks (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete.	04 nos.	each	
11.	Providing and fixing aluminium tower bolts ISI mark anodized (anodic coating not less than grade AC-10 as per IS-1868) transparent or dyed to required colour or shade with nuts and screws etc complete (A) 150 x 10 mm	30 nos.	each	
12.	Providing and fixing aluminium tubular handle bar 32 mm outer dia., 3.0 mm thick & 2100 mm long with SS screws etc. complete as per direction of Engineer-in-Charge. (a) Anodized (AC 15) aluminium tubular handle bar	10 nos.	each	
13.	Providing and fixing S.S. mesh For door partitions.	05m2	Sqm	
	Total amount (This amount is to be entered in BOQ)			
	Total taxes (if any) Including GST			
	(This amount is to be entered in BOQ)			
	Grand total			

Signature

Name of the contractor

Part: II

ABSTRACT OF COST
Name of Work:- Rewiring for Farm operation service unit (Tractor garage) at CPRS Jalandhar Punjab

S No	Description of items	Qty	Units	Rs.	Amount
1	Wiring for light points/fan points/exhaust fan points/call bell points with 1.5 sq mm FR PVC insulated copper conductor single/multi core cable in surface/ recessed steel conduits, with modular switches, modular plates, suitable GI box and earthing the point with 1.5 sq mm, FR PVC insulated copper conductor single /multi core cable etc. as required.	02	points		
2	Supplying and drawing following size FRLS PVC insulated Copper Conductor, Single core cable in the existing surface /recessed steel/ PVC conduit as required. 1.17.3 3 x 1.5 sq mm	10	meter		
3	Wiring for circuit/ submain wiring along with earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required. 1.14.2 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	10	meter		
4	Supplying and fixing following Modular switch/sockets on the modular plate and switch box including connections etc. as reqd.				
		14	Each		
	5/6 Amp. Switch	01	Each		
	15/16Amp. Switch	08	Each		
	3 pin 5/6 Amps socket outlet	01	Each		
	6 pin 15/16A socket outlet	00	Each		
	Bell Push				
5	Supplying and fixing of following size/module, GI box along with modular base and cover plates for modular switches in recess etc as reqd.				
	1.27.1 a) 1 or 2 Module (75mm x75mm)	00	Each		
	1.27.2 b) 3 Module (100mmx75mm)	00	--do--		
	1.27.3 c) 4 Module (125mmx75mm)	04	--do--		
	1.27.4 d) 6 Module (200mmx75mm)	01	--do--		
	1.27.5 e) 8 Module (125mmx125mm)	01	--do--		
	1.27.6 f) 12 Module(200mmx150mm)	02	--do--		
6	Supplying and fixing suitable size of GI Box with modular plate and cover in front on surface or in recess, including providing and fixing 6 pin 15/16A modular socket outlet and 15/16A modular switch, connection etc. As required.	01	Each		

Handwritten signature

7	Supplying, fixing suitable size GI box with modular plate & cover in front on surface or in recess including, providing and fixing 25A modular socket outlet and 25A modular SP MCB 'C' Curve including connection painting etc. as reqd. 1.57	01	Each	
	Total amount (This amount is to be entered in BOQ)			
	Total taxes (if any) Including GST (This amount is to be entered in BOQ)			
	Grand total			

K. S. Shrivastava

Name of the contractor

eProcurement System Government of India

Tender Details

Date : 13-Nov-2024 10:27 AM

Basic Details

Organisation Chain	Department of Agricultural Research and Education Indian Council of Agricultural Research,DoARE,MoA CPRI-Shimla-ICAR-DoARE Jalandhar-CPRS		
Tender Reference Number	Repair and renovation of farm operation and service unit and tractor drivers room at CPRI(RS)Jalandh		
Tender ID	2024_DARE_834749_1	Withdrawal Allowed	Yes
Tender Type	Open Tender	Form of contract	Works
Tender Category	Works	No. of Covers	1
General Technical Evaluation Allowed	No	ItemWise Technical Evaluation Allowed	No
Payment Mode	Offline	Is Multi Currency Allowed For BOQ	No
Is Multi Currency Allowed For Fee	No	Allow Two Stage Bidding	No

Payment Instruments

Offline	S.No	Instrument Type
	1	Demand Draft

Cover Details, No. Of Covers - 1

Cover No	Cover	Document Type	Description
1	Fee/PreQual /Technical/Finance	.pdf	tender document
		.xls	BOQ

Tender Fee Details, [Total Fee in ₹ * - 0.00]

Tender Fee in ₹	0.00	Fee Payable To	Nil	Fee Payable At	Nil
Tender Fee Exemption Allowed	No				

EMD Fee Details

EMD Amount in ₹	6,000	EMD Exemption Allowed	Yes
EMD Fee Type	fixed	EMD Percentage	NA
EMD Payable To	ICAR-CPRI-CPRS(RS)	EMD Payable At	Jalandhar

[Click to view modification history](#)
Work /Item(s)

Title	Repair and renovation of farm operation and service unit and tractor drivers room at CPRI(RS)Jalandh				
Work Description	Repair and renovation of farm operation and service unit and tractor drivers room at CPRI(RS)Jalandh				
Pre Qualification Details	Please refer Tender documents.				
Independent External Monitor/Remarks	NA				
Show Tender Value in Public Domain	No				
Tender Value in ₹	1	Product Category	Civil Works	Sub category	NA
Contract Type	Tender	Bid Validity(Days)	90	Period Of Work(Days)	45

Tender Inviting Authority

Name	Head, ICAR-CPRI-RS, Nakodar Road, Badshahpur, Jala
Address	ICAR-CPRI-RS, Nakodar Road, Badshahpur, Jalandhar

Tender Creator Details

Created By	AKHILESH SINGH
Designation	ACTO
Created Date	13-Nov-2024 10:16 AM