



भा.कृ.अ.नु.प.-केन्द्रीय आलू अनुसंधान संस्थान  
शिमला-171 001 (हि.प्र.)  
ICAR-Central Potato Research Institute  
(Indian Council of Agricultural Research)



ISO 9001:2015

F.No.2-15/2019/W&C/

Dated 17<sup>th</sup> Jan., 2020

### Notice Inviting Tender

The Director CPRI, Shimla invites online Limited e-tenders through CPPP from the Contractors registered with CPWD/HPWD for following work:

Name of the work	Provision of parking shed at CPRS, Kufri for Tractor & Vehicles etc.
<b>Tender ID</b>	<b>2020_DARE_537020_1</b>
Earnest Money Deposited (EMD)	Rs. 10,000/-
Bid Submission Start Date	19.01.2020 at 10:00 AM
Bid Submission Closing Date	10.02.2020 at 2:00 PM
Bid Opening Date	11.02.2020 at 2:30 PM
Bid Validity	90 days

**Note:**

1. The tender form can be downloaded from our website <http://cpri.icar.gov.in> or GOI portal <http://eprocure.gov.in>. Tender may be searched on the CPPP by using the Tender ID.

Sd/xxx  
Administrative Officer

निविदा प्रपत्र

निदेशक, केन्द्रीय आलू अनुसंधान संस्थान, शिमला निम्न कार्य हेतु CPWD/HPWD से Registered ठेकेदारों से Online Limited Tender आमन्त्रित करते हैं:-

कार्य का नाम Name of the work	Provision of parking shed at CPRS, Kufri for Tractor & Vehicles etc.
ब्याना राशि Earnest Money Deposited (EMD)	रु. 10,000/-
निविदा के प्रकार Type of Tender	Limited Tender (Single Bid)
कार्य समाप्त करने का समय Duration of completion of work	90 days
कार्य पूरा होने के बाद डिफाल्ट देयता अवधि/अवलोकन अवधि Default liability period/observation period after completion of work	90 days
आपेक्षित दस्तावेज Documents required	Amount of EMD, Bank Draft No. and date etc. entered, scanned copy uploaded and original sent to CPRI, Shimla. BOQ uploaded Financial Bid uploaded <b>Contractors, Bank Details:</b> Bank Account No., Bank Name, IFC code PAN & GST No. Proof of valid Registration with CPWD/HPWD

नियम व शर्तें:

1. निविदा Online e-Procurement के माध्यम से भेजनी होगी offline निविदाओं पर विचार नहीं किया जाएगा।
2. निविदा प्राप्त करने हेतु दिए गए समय के उपरान्त प्राप्त निविदा पर विचार नहीं किया जाएगा।
3. यदि ठेकेदार कोटेशन प्रस्तुत करने से पहले कार्य का मुआइना करना चाहें तो वह अपने खर्च पर किसी भी कार्य दिवस में सुबह 10AM से 4PM के बीच मुआइना कर सकते हैं।
4. बैंक लिस्ट में मांगे गये दस्तावेज संलग्न/अपलोड करने अनिवार्य है।
5. किसी Taxes के संबंध में किसी प्रकार की Terms & conditions न अंकित करें अतः टैक्स जो देय है साफ-साफ लिखे तथा Tax का Amount न अंकित करने की स्थिति में कोई Tax देय नहीं होगा।
6. नियमानुसार ठेकेदार के बिल से 1 प्रतिशत Worker Welfare Cess व नियमानुसार TDS की कटौती की जाएगी।
7. निविदा में कटिंग व ओवर राईटिंग नहीं होनी चाहिए यदि हो तो उस पर हस्ताक्षर करना आवश्यक है।

8. निर्धारित EMD जो DDR/FDR/Bank Guarantee के रूप में ICAR unit CPRI के नाम देय होगी जिसे निविदा खुलने की तिथि से पूर्व कार्यालय में जमा करना आवश्यक होगा । बिना EMD के अपलोड की गई निविदा पर विचार नहीं किया जाएगा ।
9. कार्यालय द्वारा जारी कार्य आदेश मिलने के बाद सात दिनों के भीतर ठेकेदार को अपनी सहमति/मंजूरी इस कार्यालय में अवश्य देनी होगी ।
10. Performance security जोकि संविदा दर की कुल 5 प्रतिशत राशि होगी कार्य समाप्त होने के पश्चात observation period तक रखी जाएगी । यह राशि Bank Draft/Bank Guarantee/FDR के रूप सफल ठेकेदार द्वारा कार्य आबंटन के 10 दिनों के भीतर संस्थान में जमा करवानी होगी ।
11. आबंटित कार्य प्रभारी, अभियन्त्रण अनुभाग की निगरानी में पूर्ण किया जाएगा ।
12. कार्य के क्रियान्वयन हेतु Estimate में दर्शाए गए सामान की गुणवत्ता से कोई भी समझौता नहीं किया जाएगा ।
13. सभी प्रकार के किए जाने वाले कार्य का भुगतान, माल की मात्रा के अनुसार प्रभारी, अभियन्त्रण अनुभाग द्वारा ली गई पैमाइश या प्रभारी अधिकारी के आदेशों के अनुसार ही किया जाएगा ।
14. यदि ठेकेदार द्वारा उक्त कार्य हेतु संस्थान का पानी इस्तेमाल किया जाता है तो उनके बिल से 1 प्रतिशत की कटौती की जाएगी ।
15. संतोषजनक कार्य पूरा करने के उपरान्त किये गये कार्य का भुगतान 60 दिन के अन्दर किया जाएगा जिस के लिए Bank detail इत्यादि देना अनिवार्य होगा ताकि E-payment द्वारा भुगतान किया जा सके ।
16. संस्थान अग्रिम राशि देय नहीं करेगा ।
17. यदि ठेकेदार या उनके कामगारों द्वारा संस्थान की प्रापर्टी को नुकसान पहुँचाया जाता है तो उस स्थिति में ठेकेदार को अपने खर्च पर उसकी भरपाई या मुरम्मत करनी होगी। यदि ठेकेदार ऐसा करने में असमर्थ पाया जाता है तो उसकी भरपाई/मुरम्मत का खर्च ठेकेदार को किए जाने वाले भुगतान में से काट लिया जाएगा ।
18. यदि ठेकेदार आबंटित कार्य को पूर्ण करने में असफल पाया जाता है तो उनके द्वारा जमा की गई performance security को जब्त कर लिया जाएगा और भविष्य में उन्हें इस संस्थान द्वारा कोई भी कार्य नहीं दिया जाएगा ।
19. यदि कार्य को करने के दौरान कार्यस्थल पर किसी मजदूर के साथ कोई दुर्घटना होती है तो उस स्थिति में ठेकेदार पूर्णतः उत्तरदायी होगा तथा ठेकेदार द्वारा सभी safety नियमों का पालन करना होगा ।
20. ठेकेदार द्वारा कार्यस्थल पर कार्यरत कर्मियों की सुविधा के लिए First Aid Box रखा जाना अनिवार्य होगा । ठेकेदार को सभी संबंधित Labour Laws का पालन करना आवश्यक होगा ।
21. Liquidated Damage: कार्य को देरी से पूर्ण करने पर Contract value का 1 प्रतिशत की दर से प्रति सप्ताह के हिसाब से व अधिकतम देरी हेतु 10 प्रतिशत के हिसाब की दर से कटौती की जाएगी ।
22. निदेशक महोदय, के पास यह अधिकार सुरक्षित है कि वह किसी भी निविदा या सभी निविदाओं को बिना कारण बताएं रद्द कर सकते हैं ।

—हस्ता—

सहायक प्रशासनिक अधिकारी (W&C)

## FINANCIAL BID

Name of work: Provision of Parking shed at CPRS-Kufri for Tractor & Vehicles etc.

SN	Item of work	Qty	Unit	Rates	Amount (Rs.)
1	Earth work in excavation by mechanical means(Hydraulic excavator)/manual means in foundation trenches or drain (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift up to 1.5 m , including getting out the excavated soil as directed within a lead of 50 m (A) All kinds of soils	18.0 m3	cum		
2	Demolishing brick work manually by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge (In cement mortar)	7.20 m3	cum		
3	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm( $\pm 0.05\%$ )total coated thickness with zinc coating 120 grams per sqm as per IS -277 , in 240 mpa steel grade 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns , Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length up to 12 meter or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x55 mm) with EPDM seal , complete up to any including cutting to size and shape wherever required.	134.0 m2	sqm		
4	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm ( $\pm 0.05\%$ ) total coated thickness , zinc coating 120 grams per sqm as per IS-277 , in 240 mpa steel grade , 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns using self drilling / self tapping screws complete.				
4A	Ridge plain (500 to 600 mm)	26.0 mtr	mtr		
5	12 mm cement plaster of mix 1:6 (1cement :6 fine sand)	25.0 m2	sqm		
6	15 mm cement plaster on the rough side of single or half brick wall of mix 1:6(1cement :6 fine sand)	25.0 m2	sqm		
7	Providing & fixing m.s welding mesh (25x25mm) thickness of wire 10 guage (weight not less than 4.0 kg/m2) complete as per the direction of In-charge Engineering section.	30.0 m2	sqm		
8	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (A)Two or more coats on new work.	152.0 m2	sqm		

9	Structural steel work in riveted , bolted , or welded in built up sections, trusses and framed work including cutting , hoisting, fixing in position and applying a priming coat of approved steel primer all complete .	1525.0	kg		
10	Steel work in built up tubular (round , square or rectangular hollow tubes etc.) trusses etc. including cutting , hoisting , fixing in position and applying a priming coat of approved steel primer including welding and bolted with special shaped washers etc. complete. (A) hot finished welded type tubes	370.0	kg		
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering -All work up to plinth level				
11 A	1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate 20 mm nominal size)	4.0 m3	cum		
11 B	1:5:10 (1 cement : 5 coarse sand :10 graded stone aggregate 40 mm nominal size)	1.70 m3	cum		
12	Half brick masonry with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in : cement mortar 1:4 (1 cement 4 coarse sand)	28.0 m2	sqm		
13	Finishing wall with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @1.67 ltr/10 sqm over and including priming coat of exterior primer applied @2.20 kg/10 sqm)	75.0 m2	sqm		
	<b>Total amount (This amount is to be entered in BOQ)</b>				
	<b>Total Taxes (if any) Including GST (This amount is to be entered in BOQ)</b>				
	<b>Grand Total</b>				

Term and Conditions:

- (1) No electricity will be provided by the Institute.
- (2) All dismantled material should be disposed at the dumping site of Municipal Corporation out of the CPRI campus. No extra payment will be made for the disposing the above material.

Name of contractor's

**List of Registered Civil Contractor's**

<b>Sl. No.</b>	<b>Name of Contractor's</b>
1	Sh. Roop Ram S/o Sh. Deep Ram R/o Vill. Jagedi P.O. Pahal Teh. Sunni, Distt. Shimla – 12
2	Sh. Ashok Verma, Govt. Contractor, Verma Cottage BCS New, Shimla 171009
3.	Sh. Jai Dev Kumar Govt. Contractor, C/O Sh. N S Thakur Set No 17 Type II CPWD Colony (Kregdu) Long Wood, Shimla 171001 HP
4	Sh. Vineet Sood, Govt. Contractor, 41, Bharari, Shimla (HP)
5.	Sh. Dasu Ram, Set no. 4, Marina Thandi Kothi, Near High Court, Shimla
6.	Er. Vineet Patial, Govt. Contractor, R/o Patial Niwas, Lower Kaithu Shimla – 171 003
7.	Sh. Roop Lal S/o Rattan Lal, C/o Smt. Nirmla, Near Labour Hostel Kachha Makan , No. 37, Phagli, Shimla- 04
8.	Sh. Dushyant Kumar, VPO Reog, Teh. Suni Distt. Shimla 171 007
9.	Sh. Rajender Singh Govt. Contractor, Vill. Parry, PO Nehra Teh & Distt. Shimla
10.	Sh. Vinod Thakur S/O Kalyan Singh, Attar Niwas Panthaghatti Kasumpti, Shimla – 171 009
11.	Sh. Rajinder Kumar, S/o Sh. Krishan Dass Verma R/o Vill. Sanula, PO Thaila, Tehsil Sunni, Distt. Shimla Correspondence Address: PO Kamla Nagar, Baustu Niwas Chhakryal Road Bhatta Kuffur, Sanjauli, Shimla 171 006 (HP)
12.	Sh. Davinder Thakur, Contractor Dev Bhawan, Old Bear Khana, Dyrption East Shimla